


REVISIONS				
ZONE	REV	DESCRIPTION	DATE	APPROVED
0	ORIGINAL		6/1/13	TEW
1	Add Ref'd Note, Modify Scope		8/23/13	TEW






Building Feed  
From 80A-3P Breaker  
(4)34, (3)H6 Gnd. In 1-1/4" C  
THHN/THWN, copper  
max. E2; Voltage Drop @ 63A


External Maintenance Bypass Panel  
WES Part # 106067  
6" From left for UPS Input (CB1)  
12" From left for UPS Output (CB3)  
MBP Input locate as required, align with above if top entry  
MBP Output locate as required, align with above if top entry  
Wall Mounted - Top of Panel 80" AFF

20 KVA Installations:  
(4)34 AVG, (3)H6 AVG Gnd. CU THHN, 1-1/4" LFMC, 109" length  
(9" pigtail at panel, 2" pigtail at UPS, gray color)  
(4)FMC Liquidtight Fittings, 90 at UPS and straight at MBP  
WES Part # 106057

(4)34 AVG, (3)H6 AVG Gnd. CU THHN, 1-1/4" LFMC, 109" length  
(9" pigtail at panel, 2" pigtail at UPS, blue color)  
(4)FMC Liquidtight Fittings, 90 at UPS and straight at MBP  
WES Part # 106058




Side View



Top View

UPS Specifications	
Output kVA	20 kVA
Output kW	18 kW
Input Voltage	120/208/3, 4W + G
Input Voltage Tolerance	177 to 239 VAC
Input Current THD	1% Full load, 2% Half Load
Input Frequency Range	43 to 67 Hz
Output Voltage	120/208/3, 4W + G
Output Voltage THD	2%
Overload Capability (on inverter)	300% for 10 seconds
Rectifier Type	15 kHz IGBT
Inverter Type	15 kHz IGBT
Battery Type	VRLA, 432 VDC
Internal Battery Reserve Time	6 minutes
Power Paths	Main, static, internal MBP, external MBP
Warranty	2 Years
PMs during Warranty	1 / Year
Heat Rejection	6000 BTU/Hr
Audible Noise	54 dBA @ 3'
On Board Controller	Color LCD, Graphical
Web/SNMP Enabled	Yes
Alarm Contacts	Yes, 6 programmable
Modbus Communications	Yes

UPS Connections Detail



Building Power Panel

Three Breaker External Bypass Panel

Critical Load

- EC Installation Scope
- 1) Provide Feed Breaker and Circuit to MBP Panel
  - 2) Provide Load Panel(s) not shown
  - 3) Provide Circuit from MBP Panel to Load Panel(s)
  - 4) Mount MBP Panel and Unistrut below MBP
  - 5) Mount UPS Module and Batteries below UPS
  - 6) All conductors to be copper
  - 7) Maintain phasing throughout - Mark each conductor at both ends prior to pulling.
- WES Scope
- 1) Provide MBP, (2) LFMC, UPS, REPD
  - 2) Deliver and set in place UPS module
  - 3) Mount and connect UPS into UPS
  - 4) Mount and connect REPD
  - 5) Check, test and startup UPS
  - 6) Provide PMs during warranty.
- Note
- 1) Circuit sizing is based upon specific UPS proposed by Wilson Engineered Systems and may not reflect alternate UPS systems which may require different sized (larger) wiring

THIS DRAWING CONTAINS CONFIDENTIAL & PROPRIETARY INFORMATION AND SHALL NOT BE DISCLOSED OR COPIED WITHOUT THE EXPRESS WRITTEN PERMISSION OF WILSON ENGINEERED SYSTEMS, INC.

Wilson Engineered Systems, Inc.  
11501 Columbia Park Drive West, Bldg 100  
Jacksonville, FL 32258

20 KVA/ 18 kW UPS  
120/208 3 Phase  
Installation Details

STATUS	SIZE	PROJECT NO.	DWG NO.	REV
FOR INFORMATION ONLY	D		W-100519 (20)	1
NOT FOR CONSTRUCTION	SCALE			SHEET 2